BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Yelahanka Division
B.B.M.P. Bangalore - 64

APPROVED TENDER SCHEDULE - B

Name of work: Improvements and construction of drains at Udayanagara in ward No- 01 of yelahanka Sub Division.

Sl. No.	Description	Unit	Approved Quantity	Rates Quoted by the Contractor Technical Manager (West) KRIDL, BBMP	
				Rate	Rate in words
1	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	cum	267.80	Rs.75.60	Rupees Seventy five and paise sixty only
2	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications,with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	cum	344.70	Rs.176.04	Rupees One hundred Six and paise four only
3	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	cum	612.50	Rs.79.10	Rupees seventy nine and paise ten only
4	KSRB-4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement at 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	82.63	Rs.5,064.12	Rupees five thousand sixty four and paise twelve only

Sl. No.	Description	Unit	Approved Quantity	Rates Quoted by the Contractor Technical Manager (West) KRIDL, BBMP	
				Rate	Rate in words
5	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications.with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	205.87	Rs.6,065.28	Rupees six thousand sixty five and paise twenty eight only
6	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Quinta	168.87	Rs.7,254.80	Rupees seven thousand two hundred fifty four and paise eighty only
7	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses ,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	sqm	1450.78	Rs.292.68	Rupees two hundred ninty two and paise sixty eight only
8	RCC Precast covering slab for drain (10cm thick) with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	sqm	288.75	Rs.1,498.00	Rupees one thousand four hundred ninty eight and paise zero only

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Yelahanka Division
BBMP, Bangalore - 64